	1.	All fire and smoke doors will be checked at the same time the fire sprinkler tests are performed.
·	2.	Check that fire doors close tightly against jamb or that double doors seat tightly against each other.
	3.	Check that smoke doors have not more than 1/8" gap.
	4.	Remove any obstructions that prevent full swing of door.
	6.	Inspect doors for holes and or damage.
	7	Check that hinge nins are properly seated and lubricate if needed

- Check that hinge pins are properly seated and lubricate if needed.
- 8. Non-electric doors: check operation of closer to ensure door closes and latches properly.
- 9. Electric doors: Check to ensure "holds-opens" are functioning properly.
- 10. If doors have a coordinator arm at top, check operation of coordinator arm to ensure proper operation.
- 11. Check for loose screws and bolts.

Annual:

12. Document any needed door repairs through the computerized work order system.